

Play ground 911

ABE CONCRETE AND EXCAVATING LLC

ESTIMATE

806 Janicki Road
Stanley, WI 54768
715-644-0626
fax # 715-644-0696

Date	Estimate #
3/6/2019	477

Name / Address:
Stanley-Boyd Area School 507 E 1st Ave. Stanley, WI 54768

PHONE

Description	Total
Project: playground	
340' 6" X 12" foot with 2 rows 3/8" rered and 6" X 12" wall with 2 rows 3/8" rered	7,900.00
6,600 sq ft base 8" and hauled in and compact to 6" (3" should show on top of wall) 14-16 yd loads of base	3,856.00
Excavation: remove 9" plus of black dirt and put around building and haul away 6 loads of black dirt to area on school property	3,300.00
1,800 sq ft 30' X 60' remove 8" and black dirt and save for around slab or haul for school to pile. 32 yds sand fill put under slab and compact and tile run to other slab. 1,800 sq ft 4" concrete with 3'8" rebar and 7 bag mix, broom finish, sawcut and sealed.	7,820.00
2 - 250' rolls 4" tile and 6 loads of sand	1,980.00
Total	\$24,856.00

As required by WI Construction Lien law, builder hereby notifies owner that persons or companies furnishing labor or materials for the construction on owners land may have lien rights on owners land and building if not paid. _____